BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHDULE-B

NAME OF WORK: Construction of culverts ravindra nagara 1st main in Shettyhalli Sub Division in ward no.13

Sl. No	Description of work	Unit	Quty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	246.24	129.60	Rupees One Hundred Twenty Nine and Sixty Paise Only
2	Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	27.70	3349.08	Rupees Three Thousand Three Hundred Forty Nine and Eight Paise Only
3	Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	110.81	3015.36	Rupees Three Thousand Fifteen and Thirty Six Paise Only
4	Providing and laying in position plain cement concrete of mix 1:2:4 using 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	12.31	4388.04	Rupees Four Thousand Three Hundred Eighty Eight and Four Paise Only
5	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Cum	184.68	66.42	Rupees Sixty Six and Forty Two Paise Only

Project Engineer (West)
K.R.I.D.L. B.B.M.P.

Signature of Contractor

Executive Engineer

6	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams.	Cum	42.48	4491.72	Rupees Four Thousand Four Hundred Ninety One and Seventy Two Paise Only
7	providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Q	50.97	5204.52	Rupees Five Thousand Two Hundred Four and Fifty Two Paise Only
8	Conveying the excavaed earth to a distance of 2kms with all lead & lifts including loading & unloading charges etc., complete.	Cum	245.00	72.71	Rupees Seventy Two and Seventy One Paise Only

Signature of the Contractor

Project Engineer (West)
K.R.I.D.L. B.B.M.P, Bangalore

Executive Engineer
Dasarahalli Division
B.B.M.P